



# Railway substructure evaluation using FWD – main issues

- MEASUREMENT SYSTEM - STUDIES PERFORMED ON AN EXISTING RAILWAY LINE
- CLIMATIC INFLUENCE - TESTS PERFORMED DURING CONSTRUCTION OF SUBSTRUCTURE
- LOAD INFLUENCE - TESTS PERFORMED ON PHYSICAL MODEL – GRANULAR VS BITUMINOUS
- INTERPRETATION - BACK-CALCULATION OF GRANULAR MATERIAL LAYERS
- CONCLUSIONS



# MEASUREMENT SYSTEM

## STUDIES PERFORMED ON AN EXISTING RAILWAY LINE

- FWD UPGRADE TO RAILWAYS
- LOAD PLATE ADAPTED TO MEASURE ON BALLAST



# STUDIES PERFORMED ON A OLD RAILWAY LINE

- The experimental studies presented in this work aimed to **construct and evaluate four solutions for structural reinforcement of old railway tracks**, maintaining the ballast layer as structural layer.
- **Ballasted track section**
  - 36 m long, (4 experimental sections)
  - Iberian gauge (1.668 m)
  - bi-block sleepers
  - limestone ballast.



# Before reinforcement

- FWD upgrading for railways tests



# Load tests – PLT and FWD before reinforcement

## FWD

0.40 m diameter plate/ 500 kPa


## Plate load tests (PLT)

0.45m diameter plate / 200 kPa







## PLT & FWD results

Deformation moduli (E)  $E = 0.75 \cdot d \frac{P}{\delta}$



- 60 - 80 MPa existing
- 120 MPa design

# GPR results on experimental sections



# Load tests on experimental sections

## LFWD on the subgrade



- 0.30 m diameter plate
- 200 kPa
- $E \sim 70-80 \text{ MPa}$ .


## FWD on the top of the reinforcement





- 0.30 m diameter plate
- 400 kPa
- 2 FWD test series
  - August
  - September




# FWD results on experimental sections



# FWD results on experimental sections



— August  
— September




# Backcalculation of FWD results

Deformation moduli obtained E (Mpa)

	FWD-August E (MPa)	FWD-September E (MPa)
Cement bound granular material (CBGM)	600	500
Unbound granular material (UGM)	150	120
UGM mixed with ballast (UGM+B)	180	160
Fouled Ballast (FB)	180	160
Subgrade (SG)	80	60

- UGM and fouled ballast modulus are adequate and similar to resilient modulus obtained in triaxial tests
- Subgrade soil modulus is similar to the LFWD results.
- Cement bound granular material modulus is low probably due to the difficulty of adequately mix the materials on site
- Decrease in the modulus values after rainfall: subgrade soils, UGM.

# Backcalculation of FWD results



DIFFICULTIES IN BACKCALCULATION

## CLIMATIC INFLUENCE

### TESTS PERFORMED DURING CONSTRUCTION OF SUBSTRUCTURE

- E MODULI INCREASE DURING DRY WEATHER SIGNIFICANTLY
- MEASUREMENT PROBLEMS - DEFLECTION MEASUREMENT
- MEASUREMENT PROBLEMS - INCREASE NUMBER OF DROPS UNTIL DEFLECTIONS STABILISE
- DIFFICULTIES IN BACKCALCULATION




## CLIMATIC INFLUENCE

### TESTS PERFORMED DURING CONSTRUCTION OF SUBSTRUCTURE

Falling Weight Deflectometer (FWD) tests were undertaken during the construction of a **29 km new railway line**, at the top of the substructure and in different months **November , December, January and March (June)**


- **Quality control** during construction.
- Analyse and compare test results for **different climatic conditions**



## CLIMATIC INFLUENCE

### TESTS PERFORMED DURING CONSTRUCTION OF SUBSTRUCTURE

- NDT tests were performed at the top of the sub-ballast layer



## CLIMATIC INFLUENCE

### TESTS PERFORMED DURING CONSTRUCTION OF SUBSTRUCTURE

- Several load levels
  - in service traffic
  - construction traffic
- Testing campaigns in different seasons



### Several other tests were performed

- PLT
- HFWD
- Portancemetre



LABORATÓRIO NACIONAL  
DE ENGENHARIA CIVIL


Railway substructure evaluation using FWD  
Simona Fontul



## CLIMATIC INFLUENCE


### TESTS PERFORMED DURING CONSTRUCTION OF SUBSTRUCTURE

Section	A1	A2	B	C	D
Sub-ballast (granite)	0.30 m	0.15 m	0.30 m	0.30 m	0.30 m
Capping layer (limestone)	0.20 m	0.35 m	0.35 m	0.50 m	0.40 m
Subgrade	0.80 m	0.80 m	0.65 m	0.50 m	0.60 m




# GPR MEASUREMENT

- Change in layer thickness







# CLIMATIC INFLUENCE

## TESTS PERFORMED DURING CONSTRUCTION OF SUBSTRUCTURE



# CLIMATIC INFLUENCE



## TESTS PERFORMED DURING CONSTRUCTION OF SUBSTRUCTURE



# CLIMATIC INFLUENCE

## TESTS PERFORMED DURING CONSTRUCTION OF SUBSTRUCTURE


Deformation modulus values



## CLIMATIC INFLUENCE

### TESTS PERFORMED DURING CONSTRUCTION OF SUBSTRUCTURE

Sec	RP	Nov	Dec	Jan	Mar
A1	2600	296	232	143	238
A2	18100	298	305	202	318
B	3600	613	691	314	484
C	3800	-	594	265	497
D	17600	395	362	231	405




- It can be observed that the values obtained in November and December are quite similar, while in **January** they are **30 to 50% lower** than those obtained in November.
- Then, in March, the deformation modulus values tend to increase again to values closer to the ones obtained in the first two campaigns.


# CLIMATIC INFLUENCE

## TESTS PERFORMED DURING CONSTRUCTION OF SUBSTRUCTURE

- Backcalculated sub-ballast elastic moduli variation with load peak November vs June



**November**



# LOAD INFLUENCE

## TESTS PERFORMED ON PHYSICAL MODEL

- E MODULI INCREASE WITH LOAD
- MEASUREMENT PROBLEMS - DEFLECTION MEASUREMENT
- MEASUREMENT PROBLEMS - INCREASE NUMBER OF DROPS UNTIL DEFLECTIONS STABILISE
- DIFFICULTIES IN BACKCALCULATION






# LOAD INFLUENCE

## TESTS PERFORMED ON PHYSICAL MODEL

- Two different substructures were reproduced in physical models, with different subballast materials:
  - Traditional solution – 0.30m granite unbound granular material (UGM)
  - Italian HSL solution – 0.12m bituminous material
- Cells dimension: 4.0x2.0m<sup>2</sup> by 2.8m depth







# Non destructive tests

- Non destructive tests
  - Falling Weight Deflectometer (FWD)
  - Ground Penetrating Radar (GPR)
- > FWD tests location
  - six locations (A, B, C, D, E and F)
  - spaced approximately by 0.50 m
- > FWD tests characteristics
  - nine transducers (D1 to D8)
  - 30 mm load plate (segmented)
  - Stress levels applied (160 to 520 kPa)



# LOAD INFLUENCE

## TESTS PERFORMED ON PHYSICAL MODEL




# LOAD INFLUENCE

## TESTS PERFORMED ON PHYSICAL MODEL


- E 1 moduli for top layer

### C1 - Força 25 kN



**GRANULAR**

### C2 - Força 25 kN




**BITUMINOUS**




# LOAD INFLUENCE

Five levels of loading were applied:  
**25, 50, 75, 90 e 120 kN**

**GRANULAR**



**BITUMINOUS**



# Railway evaluation using FWD

## DEBATE

- MEASUREMENT SYSTEMS ON RAILWAY LINES ??
  - TEST LOCATION
  - GEOPHONES POSITION ON SURFACE
- CLIMATIC INFLUENCE
  - THE E MODULI CAN BE SO DIFFERENT?? (5 X)
  - LIMESTONE GRANULAR E > 1000 MPa
  - HOW YOU CORRECT THE VALUES ACCORDING TO SEASON??
- LOAD INFLUENCE– GRANULAR VS BITUMINOUS
  - HOW YOU CORRECT THE VALUES ACCORDING TO SEASON??
- TESTING AND INTERPRETATION
  - TESTING PROCEDURE, NUMBER OF DROPS , NUMBER OF TESTS , GEOPHONES POSITION ON SURFACE
  - BACK-CALCULATION OF GRANULAR MATERIAL LAYERS.



**Thank you for your attention!**

[simona@lnec.pt](mailto:simona@lnec.pt)

