



LINESOYA PASSIVE HOUSE **Group 4** Lin Du, Arjun Basnet, Tina Viklund

Site study










Getting Started



Concept: "Cuddling for energy efficiency"

The assigned design project is situated in Linesøya, an island at the Atlantic coast at the end of the Trondheimfjord. Until the construction of the bridge is completed, the island can only be reached by a ferry from the neighboring island Stokøya. The existing building is in fact in a good state even though it has been built back around 1950. Our concept here is to retrofit the house with an envelop of insulation wraping it around to keep it warm as a mother does to her child and we have termed it as cuddling- "cuddling for energy efficiency. There is not much intervention needed. Wrapping it around with extra "layer" could improve its efficiency in terms of energy use. Additions to the south are arranged such that there is ample penetration of sunlight.





LINESOYA PASSIVE HOUSE "Cuddling for energy efficiency" EXISTING COSTO-CARS ENTRANCE BUILDING SUNSPACE

"Cuddling for energy efficiency"


Site Plan

- Access leads the visitors to the parking which is to the south from where one can have a panoramic view of the house.
- Parking is divided into private and public.
- •The walkways connect the parking to the building.
- •Additions to the original building is done such that maximum sunlight utilized.
- •Green areas are retained with further additions.
- •The site is articulated as per international design.
- •Eco-garden which uses the grey water from the building is to the north.




"Cuddling for energy efficiency"

Plans




"Cuddling for energy efficiency"

Plans




"Cuddling for energy efficiency"


<u>Plans</u>




"Cuddling for energy efficiency"

Elevations









"Cuddling for energy efficiency"


Elevations






"Cuddling for energy efficiency"

Sections




"Cuddling for energy efficiency"


Sections




"Cuddling for energy efficiency"




OUTSIDE - NSIDE
22 MM CLADDING PINE HEARTWOOD
30 MM HORSONTAL FURRING
2X36 MM FURRING
ROOF MEMBRANE
80 MM ROCKWOOL
300 MM XPS
VAPOUR RETARDER SD2
6 MM WOOD FIBRE BOARD
98 MM SQLD WOOD







"Cuddling for energy efficiency"

Details







INSIDE - OUTSIDE
MDF DENSE FIBRES GLUED
60 MM SOLID WOOD
PAPER
10 MM INSULATION
PAPER
50 MM MINERAL WOOL
30 MM WOODEN WALL PLATE
BLACK PAPER
42 FRAMEWORK INSULATION
200 MM EPS
28 MM FURRING
22 MM HEARTWOOD PINE CLADDING

INSIDE - OUTSIDE STUCCO 50 MM FIBERCEMENT 290 MM CONCRETE 200 MM MORTAR 200 MM EPS 28 MM FURRING 22 MM HEARTWOOD PINE CLADDING

"Cuddling for energy efficiency"

Main View



"Cuddling for energy efficiency"

Views









"Cuddling for energy efficiency"

Passive strategies

- Orientation of the sunspace
- Thermal mass
- Insulation
- Natural ventilation

Active strategies:

PV Crystalline PV (on the roof)

Nominal power: 340W

Area: almost 150m2

Solar thermal collector (on the roof)

Efficiency: 60%

Area: approximately 26m2

Heat pump

Set temperature: 50 C

COP: 2.8

- Wind turbine (in suitable location near site)
- Heat recovery system

Energy budget:

For the energy calculation of this project, we divided this building into three different zones which are residential (106.6m2), culture/office (198.2m2) and sport area (159.6m2). So the total heated floor area is 464.4 m2.

Heating demand calculations:

Our main focus has been to document the design's potential to reach the passive house standard, which is less than 21.74 kWh/m2 energy use in the building for space heating. For accuracy, we divided the model into four thermal zones and programmed different thermal temperatures and schedules for each zone. To estimate internal heat gains we also made a rough assumption of the amount of people using each zone.

From the result, we can see that the building meets the space heating demand of passive house standard, which is 19.2 KWh/m2.

Heat balance

From the graph of the heat balance of the building, solar thermal collector and heat pump could provide enough heating demand for the house. In the summer, it produces much more heat which could be storage. But, in the winter, there should be some heat complemented by the electricity grid.


From the chart of electricity balance, the house needs some energy from electrical grid during the winter, and in the summer, the house will produce surplus electricity which could be sold to the grid.

CO₂ emissions

The chart shows that the CO2 emissions of the building from the energy perspective. In summer, the building could produce much more green electricity which could be sold to the grid; thereby compensating CO2 production during winters.


"Cuddling for energy efficiency"

Strategies



"Cuddling for energy efficiency"

Strategies



"Cuddling for energy efficiency"

Wind turbine

General


Axis	Vertical
Height	4.60 m (15.10 ft)
Width	3.00 m (9.85 ft)
Weight	461 kg (1016 lb)
Swept Area	13.8 m ² (149 ft ²)

Blade Materials _____ Carbon Fiber and Fiberglass



Rated Power	4000 W
Cut-in Wind Speed	3.5 m/s (7.8 mph)
Cut-out Wind Speed	30 m/s (67 mph)
Rated RPM	110 RPM
Survival Wind Speed	55 m/s (123 mph)
Rated Wind Speed	12 m/s (27 mph)
Noise Level at 12 m/s	49 dB

UGE-4K Annual Power Output





Annual Average Wind Speed (m/s) I m/s = 22 mph


Energy Budget

	heat		electricity		total
	Net energy demand [kwh/a]	Specific energy demand [kwh/(m²a) (464.4m²)]	Net energy demand [kwh/a]	Specific energy demand [kwh/(m²a) (464.4m²)]	
heating	10093.768	21.74			
domestic hot water(DHW)	12119.0918	26.10			
fans			4820.724	10.38	
pumps			1441.44	3.10	
lighting			6430.144	13.85	
technical equipment			4876.782	10.50	
cooling					
sum	22212.8598		17569.09		39781.95
		47.83		37.83	85.66


"Cuddling for energy efficiency"









	HEATING	COOLING	TOTAL
MONTH	(Wh)	(Wh)	(Wh)
Jan	1667302	0	1667302
Feb	1505826	0	1505826
Mar	1358103	25953	1384056
Apr	684460	70939	755398
May	317166	375289	692455
Jun	13253	425503	438756
Jul	6498	695363	701862
Aug	5775	760896	766671
Sep	66788	348524	415312
Oct	117361	60807	178168
Nov	946406	24155	970561
Dec	2226450	3524	2229974
TOTAL	8915389	2790952	11706342
PER M	19197.6507	6009.80189	41.3386105
Floor Area:	464.4	m2	



"Cuddling for energy efficiency"





Total CO2 emissions(kg)

